

incite™





DIMENSIONAL DRAWINGS

FIX WALL ARM

max 415 mm

WALL FIXED DRENCHER


300mm

97mm 97mm


CONTROLLER

48.5mm


SMARTVALVE








HAND SHOWER AND BRASS WALL OUTLET











REMOTE









WITH HAND SHOWER AND WALL FIXED DRENCHER - HP/COMBI

TECHNICAL SPECIFICATIONS

| Minimum pressure requirements | 1 bar |
|------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------|
| Maximum pressure requirements | 7 bar |
| SmartValve inlet fitting connections | 15mm push fit fittings, valve inlet centres 48mm, inlet supply positions – hot right, cold left |
| SmartValve and diverter outlet connections | 15mm push fit |
| Permissible SmartValve and diverter siting locations | Loft, airing cupboard, under bath |
| Supply temperature | Cold inlet temperature 1°C (minimum) Cold inlet temperature 15°C (maximum) Hot inlet temperature 65°C (maximum) |
| Water system | HP / Combi / Boosted gravity |
| Features | One touch start/stop control |
| | LED display indicates when pre-selected temperature has been reached |
| | Wi-Fi & App compatible – control your product with your smart phone and smart home device e.g. Alexa |
| | App functions include start/stop, shower timer, user dashboard, usage tracker and help & support |
| | SmartValve |
| | Digital diverter technology |
| | 300mm drencher and slim hand shower |
| | Compatible with wired remote control |
| Guarantee period | 5-year guarantee - shower unit |
| | 2-year guarantee - shower head and kit |
| Approvals | CE Marking |
| | UKCA |
| | BEAB |